



# Trailer-Mounted Twin Cementing Units

Precise uses triplex pumps mounted in a back to back configuration. Available pumps are SPM, GD, Serva and Demay. Trailer: Heavy beam drop deck design. Drop deck allows engine position to distribute unit weight as equal as possible to drive and trailer axles. Drop deck also lowers the center of gravity allowing for safer transportation of equipment.



Precise utilizes the time proven RCM mix system. The system is designed electric over hydraulic for infinite control of the slurry delivery system. Micro-Motion fluid densitometer is utilized for precise customer product delivery. Fully computerized mixing system available upon request.

## Control Panel

System flow schematic incorporated into control panel for ease of operation. Standard engine transmission controls. Double redundant hydraulic system selected by operating a single switch. Rate, pressure and speed indication gauges via analog and/or digital displays. Training/Commission of unit to be conducted at customer location.



Corporate:  
131 East Exchange Avenue, #104  
Fort Worth, Texas 76164

Plant:  
3201 North Sylvania Avenue, #605  
Fort Worth, Texas 76111

Phone: 817-439-1972  
Fax: 817-479-9206  
[www.PreciseEnergyProducts.com](http://www.PreciseEnergyProducts.com)